(*l*) The bills for carting should be supported by the receipts. The carting for one full month should be claimed in a single bill to be presented in the next month and no part payment will be allowed in the middle of the month. No claim for the cart-hire not claimed within three months from the date of its becoming due will be paid unless the delay in claiming is satisfactorily explained.

(*m*) The security furnished will be returned to the contractor three months after the expiry of the contract period, if the whole or any portion of it is not forfeited to Government for the violation of any of the terms of the contract, after satisfying that no poles are outstanding against the contractor.

SCHEDULE.

| Sl. No. | Place of Collection | Siding to which to cart | Approximate lead | Approximate No. required | | |
|---|---|---|---|---|---|---|
| | | | | 35′ | 30′ | 26′ |
| 1 | Kuskal forest coupes 1, 2 and 3 .. | Agasanahadlu .. | 15 miles | 100 | 200 | 1,000 |
| 2 | Megarmakki .. | Do .. | 20 ,, | 100 | 100 | 500 |
| 3 | Lakkavally State Forest—Jambe and Mathi. | Do .. | 7 ,, | .. | 100 | 500 |
| 4 | Lakkavally Coppice with Reserves coupe and plantation area. | Haruvanahalli Siding. | 5 to 7 ,, | .. | 100 | 500 |

*N.B.*—In the case of (1), (2) and (3) only Jambe, Hunal and Dindiga should be felled and no other kinds will usually be felled. Felling should be completed before the 15th October 1940.

(*ii*) In the case of (4) Mathi and Nandi may also be felled in addition.

(*iii*) The number given in the schedule above are only approximate.

H. S. RANGACHAR,
*District Forest Officer.*

## KADUR FOREST DIVISION.

*Resale Notification dated 5th July* 1940.

It is hereby notified for general information that the exclusive right of collecting the Minor Forest Produce on all Government unoccupied lands, Amrit Mahal Kavals, State Forests, Reserved lands and Plantations for two years from 1st July 1940 to 30th June 1942, in the undermentioned Taluks will be sold Talukwar by public auction at 2 P.M. on the date and at the place specified below, as the sale held on 24th June 1940 is not confirmed.

| Name of Taluk | Place of sale | Date of sale | Officer conducting the sale |
|---|---|---|---|
| 1. Koppa Taluk .. | District Forest Office, Chikmagalur. | 23rd July 1940 .. | District Forest Officer |
| 2. Mudgere Taluk .. | Do .. | Do .. | Do |

For conditions of sale and other particulars *vide* Notification No. D1-63-981—39-40, dated 15th April 1940, published by the Chief Conservator of Forests in Mysore, Bangalore, in Part VI, pages 895-99 of the *Mysore Gazette*, dated 18th April 1940.

B. T. THIMMARAYAPPA,
*District Forest Officer.*

# ENGINEERING DEPARTMENT

## BUREAU OF SANITARY ENGINEERING, BANGALORE.

*Notification dated 3rd July* 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 26th July 1940, for the work of

constructing drains in Chennarayapatna town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer on a payment of annas four per form. No tender of non-prescribed form will be accepted. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 56 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of constructing drains in Chennarayapatna town", in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the approximate quantities for the work of constructing drains in Channarayapatna Town.

| No. | Name of work | Unit | Quantity |
|---|---|---|---|
| | I. | | |
| 1 | Constructing silk pattern drains with 3″ to 4″ thick slabs dressed for the cheeks and cement concrete 1 : 2 : 4 for the sides and bed 1½″ thickness over 3″ thick surki concrete bed and surface plastered with ½″ thick cement mortar in the proportion of 1 : 3 and cement pointing the stone slabs including earthwork, forming, etc., as per design | | |
| | Design of 3″ section with new slabs | R.ft. | 900 |
| 2 | Constructing 3″ section semi-peg top drains with cement concrete in the proportion of 1 : 2 : 4 on 3″ thick surki concrete bed and surface plastered with ½″ thick cement mortar in the proportion of 1 : 3 including earthwork forming, etc., complete as per design | ,, | 980 |
| | II. *Constructing tunnels.* | | |
| 1 | Earthwork excavating the foundation | C.yd. | 13 |
| 2 | New size stone in surki mortar | C.ft. | 234 |
| 3 | Cement pointing to stone masonry | Sqr. | 1·20 |
| 4 | Providing and fixing new covering slabs 5″ to 6″ thick, cement pointing the joints, the end slabs dressed | S.ft. | 240 |

K. S. HUTCHA RAO,
*Sanitary Engineer.*